HILLSIDE LN.		States ST.	PROJECT SITE	PSTATE S		
	<u> </u>	SCALE: NTS	AP			
			יבא]	
SHEET		<u>SHEET INL</u>		REVISION		
<u>NO.</u>	SHEET N	AME		DATE		
C0.0	COVER	750	12/01/2023	2/16/2024	-	
C0.1 C1.0	GENERAL NO	NDITIONS & DEMO PLAN	12/01/2023 12/01/2023			
C2.0	PLAN & PROF	FILE (SHEET 1 OF 7)	12/01/2023		-	
C2.1	PLAN & PROF	FILE (SHEET 2 OF 7)	12/01/2023		-	
C2.2	PLAN & PROF	FILE (SHEET 4 OF 7)	12/01/2023		_	
C2.4	PLAN & PROF	FILE (SHEET 5 OF 7)	12/01/2023		-	
C2.5	PLAN & PROF	FILE (SHEET 6 OF 7)	12/01/2023		-	
C3.0	PLAN DETAIL	S (SHEET 1 OF 3)	12/01/2023		-	
C3.1	PLAN DETAIL	S (SHEET 2 OF 3)	12/01/2023		-	
C3.2		S (SHEET 3 OF 3)	12/01/2023		-	
C4.0	CROSS-SECT	IONS (SHEET 1 OF 5)	12/01/2023		-	
C4.1	CROSS-SECT	IONS (SHEET 2 OF 5)	12/01/2023		-	
C4.2	CROSS-SECT	IONS (SHEET 3 OF 5)	12/01/2023		-	
C4.3 C4.4	CROSS-SECT	IONS (SHEET 5 OF 5)	12/01/2023		-	
C5.0	EROSION CO	NTROL PLAN (SHEET 1 OF 1)	12/01/2023	2/16/2024	-	
C5.1	EROSION CO		12/01/2023		-	
C6.1	TRAFFIC CON	ITROL DETAILS (SHEETS 1 OF	1) 12/01/2023			
ENGINEEF ADDRESS	RING FIRM: S:	<u>ESP ASSOCIATES, INC.</u> 3475 LAKEMONT BLVD.				
PHONE:		FORT MILL, SC 29708 (803) 802-2440				
FAX: CONTACT	:	(802) 802-2515 ANDREW MARTIN, PE				
ADDRESS	S :	10 N ROOSEVELT ST.				
PHONE:		(803) 684-2341				
CONTACT	:	BEN WRIGHT				
REVIEWIN ADDRESS	IG AGENCY: S:	CITY OF YORK PLANNING 10 N ROOSEVELT ST. P.O. YORK, SC 29745	& DEVELOPMENT BOX 500			. \
PHONE:		(803) 684-2341			\	```
<u>REVIEWIN</u> ADDRESS PHONE:	IG AGENCY: 3:	<u>SCDOT DISTRICT 4</u> 1232 J A COCHRAN BYPA CHESTER, SC (803) 385-4280	SS		\backslash	$\langle \rangle$
REVIEWIN		SCDHEC			\	N VIK
ADDRESS PHONE:	5:	2600 BULL STREET COLUMBIA, SC (803) 898-3432				
			" UDE ,	<u>َ</u> \ ۱		
<u>UTILITY P</u>	ROVIDERS:		44			· ····································
	<u>CITY:</u> S:	DUKE ENERGY 550 TRYON STREET				
		CHARLOTTE, NC 28202 (704) 812-2316			NV I	1
	NE)		I
ADDRESS	8:	P.O. BOX 470			CON	
PHONE:		RUUN HILL, SU 29730 (888) 403-2667			S'RES.	
	<u>- GAS:</u> S:	YORK COUNTY NATURAL 979 W. MAIN ST ROCK HILL, SC 29730	. GAS AUTHORITY		STREE	
PHONE: <u>WATER &</u> ADDRESS	<u>a SEWER:</u> 3:	(803) 323-5304 <u>YORK COUNTY WATER A</u> 6 S. CONGRESS ST. YORK SC 20745	ND SEWER			٢٧.

LINCOLN ROAD SIDEWALK LOCATED IN CITY OF YORK, SOUTH CAROLINA



PALM

THIS SET IS CURRENT THROUGH SHEET DATE 2/16/2024

GRAPHIC SCALE

(IN FEET) 1 INCH = 150 FT.

PROFESSIONAL'S CERTIFICATION (SCDHEC SWPPP)

I have placed my signature and seal on the design documents submitted signifying that I accept responsibility for the design of the system. Further, I certify to the best of my knowledge and belief that the design is consistent with the requirements of Title 48, Chapter 14 of the Code of Laws of SC, 1976 as amended, pursuant to Regulation 72-300 et seq. (if applicable), and in accordance with the terms and conditions of SCR100000. I also certify that this plan is designed to contain sediment on the property concerned and to provide for the control of stormwater runoff from the property and that, to the best of my knowledge and belief, all the provisions are in accordance with Chapter 152 - Stormwater Management and Sediment Control of the York County Code of Ordinances.

DATE Registered Landscape Architect





	ESP Associates. Inc	P.O. Box 7030 Charlotte, NC 28241	3475 Lakemont Blvd. Fort Mill, SC 29708	704-583-4949 (NC)	003-002-2440 (3C) www.espassociates.com	
					このとうどうとうとうこと	
ВΥ	TWD					
DATE REVISION	2/16/2024 EROSION CONTROL UPDATE: SEDIMENT TUBE SHIFT					
NO.	٦					
COVER		TY OF YORK			YORK, SC YORK	
PRC	PRC	DJECT MANA	INFO	RMAT	TION BAN	C
DESIGNED BY: DRAWN BY: PROJECT NUMBER: ORIGINAL DATE:			1	DM/ DM/ KT14.4 2/01/2	A A 400 2023	

C0.0

GRADING NOTES:

1. EXISTING TOPOGRAPHIC INFORMATION TAKEN FROM SURVEY PROVIDED BY GPA, INC. DATED 01/05/2023.

2. CONSTRUCTION **SHALL NOT** BEGIN PRIOR TO A PRELIMINARY CONSTRUCTION INSPECTION OF THE SITE. CONTACT THE CITY OF YORK AT LEAST 48 HOURS PRIOR TO BEGINNING CONSTRUCTION FOR INSPECTION.

3. CONTRACTOR IS RESPONSIBLE AT CONTRACTOR'S EXPENSE FOR ENSURING AND OBTAINING ALL NECESSARY PERMITS AND APPROVALS PRIOR TO CONSTRUCTION. THESE PERMITS MAY INCLUDE BUT NOT LIMITED TO; GRADING, DEMOLITION, BLASTING, ZONING, BUILDING, DRIVEWAY, DETENTION, SUBDIVISION SPECIAL USE, WATER AND SEWER PERMITS AND APPROVALS.

4. CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR CONTACTING ALL APPROPRIATE UTILITIES AND ENSURING THAT UTILITIES ARE LOCATED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION ACCORDING TO SC STATE LAW. CONTRACTOR SHALL VERIFY LOCATION AND DEPTHS OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.

5. WHEN UNDERGROUND OBSTRUCTIONS NOT SHOWN ON THE CONSTRUCTION DRAWINGS (ROCK. PIPING, ETC.) ARE ENCOUNTERED, THE CONTRACTOR SHALL PROMPTLY REPORT THE CONFLICT TO THE OWNER'S REPRESENTATIVE. ALL CHANGES MUST BE APPROVED IN WRITING BY THE OWNER OR HIS REPRESENTATIVE BEFORE CONSTRUCTION CAN PROCEED.

6. CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR REPAIR AND/OR REPLACEMENT OF ANY UTILITIES DAMAGED DURING CONSTRUCTION.

7. ROAD SHOULDERS, SWALES, BACK-OF-CURBS, AND CUT/FILL BANKS SHALL BE COMPLETELY DRESSED BY THE CONTRACTOR AND SEEDED AS SOON AS POSSIBLE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF THESE AREAS UNTIL A PERMANENT STAND OF GRASS IS ESTABLISHED.

8. CUT AND FILL SLOPES OF ANY AREA SHALL NOT EXCEED THE RATIO OF 2:1, UNLESS NOTED OTHERWISE. FILL SLOPES GREATER THAN EIGHT (8) VERTICAL FEET SHALL HAVE PERMANENT SEED/SLOPE MATTING INSTALLED.

9. ACCESS DRIVES AND PARKING AREAS SHALL BE GRADED IN ACCORDANCE WITH THE LINES AND GRADE SET BY THE ENGINEER. BEFORE PLACING CURB AND GUTTER OR BASE ON THE GRADED SUBGRADE, THE SUBGRADE SHALL BE COMPACTED TO 100% PER ASTM D698 FOR A DEPTH OF TWELVE (12) INCHES, 95% GREATER THAN TWELVE (12) INCHES, AND THEN SHALL BE PROOF ROLLED IN THE PRESENCE OF THE ENGINEER. PLACES THAT ARE FOUND TO BE LOOSE, SOFT, OF COMPOSED OF UNSUITABLE MATERIALS. WHETHER IN THE SUBGRADE OR BELOW IT. MUST BE DUG OUT AND REFILLED WITH SUITABLE MATERIAL. ALL EMBANKMENTS OR FILLS SHALL BE MADE IN SIX-INCH HORIZONTAL LIFTS OF SUITABLE MATERIAL. THE FILL SHALL BE ROLLED WITH A SHEEPS-FOOT ROLLER AFTER EACH LIFT, FOLLOWED BY A WHEEL ROLLER, EACH WEIGHING NOT LESS THAN TEN (10) TONS.

10. THE STONE BASE SHALL BE COMPACTED TO 100% OF THE MAXIMUM DENSITY OBTAINABLE WITH THE MODIFIED PROCTOR TEST (AASHTO-T180) BY ROLLING WITH RING OR TAMPING ROLLER OR WITH A PNEUMATIC TIRED ROLLER WITH A MINIMUM WEIGHT OF TEN TONS. WHEN COMPLETED. THE BASE COURSE SHALL BE SMOOTH, HARD, DENSE, UNYIELDING AND WELL BONDED.

11. FILL EMBANKMENTS SHALL BE FORMED OF SUITABLE MATERIAL PLACED IN SUCCESSIVE LAYERS NOT TO EXCEED MORE THAN SIX (6) INCHES IN DEPTH FOR THE FULL WIDTH OF THE CROSS-SECTION INCLUDING THE WIDTH OF THE SLOPE AREA NO STUMPS TREES BRUSH RUBBISH OR OTHER UNSUITABLE MATERIALS OR SUBSTANCES SHALL BE PLACED IN THE EMBANKMENT. EACH SUCCESSIVE SIX (6) INCH LAYER SHALL BE THOROUGHLY COMPACTED BY THE SHEEPS-FOOT TAMPING ROLLER, 10-TON POWER ROLLER, PNEUMATIC-TIRED ROLLER, OR OTHER METHODS APPROVED BY THE ENGINEER. EMBANKMENTS OVER AND AROUND ALL PIPE CULVERTS SHALL BE OF SELECT MATERIAL, PLACED AND THOROUGHLY TAMPED AND COMPACTED AS DIRECTED BY THE ENGINEER.

12. ALL BACKFILL SHALL BE NON-PLASTIC IN NATURE, FREE FROM ROOTS, VEGETATIVE MATTER, WASTE, CONSTRUCTION MATERIAL, AND OTHER OBJECTIONABLE MATERIAL. SAID MATERIAL SHALL BE CAPABLE OF BEING COMPACTED BY MECHANICAL MEANS AND THE MATERIAL SHALL HAVE NO TENDENCY TO FLOW OR BEHAVE IN A PLASTIC MANNER UNDER THE TAMPING BLOWS OR PROOF ROLLING.

13. CONTRACTOR SHALL REPORT ANY DISCREPANCIES BETWEEN FIELD CONDITIONS AND THESE PLANS TO THE ENGINEER IMMEDIATELY.

14. CONTRACTOR SHALL TIE ALL PROPOSED PAVEMENT FLUSH TO EXISTING PAVED SURFACES.

15. THE DESIGN OF ALL ROADS, SANITARY SEWAGE, STORM DRAINAGE PIPING AND DITCHES, AND WATER QUALITY DETENTION FEATURES PRESENTED HEREIN HAS BEEN COMPLETED FROM FIELD SURVEY INFORMATION.

16. REFER TO STORM DRAIN PLANS AND PROFILES FOR ADDITIONAL INFORMATION ON PROPOSED STORM DRAINAGE SYSTEM

17. CONTRACTOR SHALL ADJUST ALL EXISTING STRUCTURE LIDS, RIMS, GRATES, AND COVERS TO BE FLUSH WITH SURROUNDING PAVEMENT

STORM DRAINAGE NOTES:

1. THE MINIMUM DESIGN FREQUENCY FOR STORM RUNOFF SHALL BE THE 10-YEAR STORM FOR STORM DRAINAGE COLLECTION.

2. ALL STORM DRAINAGE PIPE SHALL BE REINFORCED CONCRETE UNLESS OWNER REQUESTS OTHER TYPE MATERIAL, NO PIPE SHALL BE SMALLER THAN 15-INCHES IN DIAMETER. NO PIPE OUTSIDE OF PAVEMENT AREAS SHALL HAVE LESS THAN 24-INCHES OF COVER MEASURED FROM THE OUTSIDE DIAMETER OF THE PIPE. NO PIPE WITHIN PAVEMENT AREAS SHALL HAVE LESS THAN 36 INCHES OF COVER MEASUERED FROM THE OUTSIDE DIAMETER OF PIPE . IF THE CONDITIONS ABOVE CAN NOT BE MET THE RCP SHALL BE CLASS IV PIPE.

3. CULVERT OUTLET PROTECTION AND SWALE EROSION PROTECTION SHALL BE DESIGNED BASED ON A 10-YEAR STORM.

4. STORM DRAINAGE STRUCTURES AND PIPES SHALL BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH SCDOT SPECIFICATIONS, CITY OF YORK, AND SCDHEC.

5. STORM DRAINAGE SYSTEMS MUST MEET CITY OF YORK AND SCDHEC STANDARDS FOR STORMWATER MANAGEMENT AND SEDIMENT REDUCTION

6. UNDER DRAINAGE SHALL BE PROVIDED AS DIRECTED BY OWNERS' INDEPENDENT TESTING FIRM, IF NECESSARY. DETERMINATION SHALL BE MADE IN THE FIELD.

7. CONCRETE MORTAR JOINTS SHALL BE USED FOR JOINING ALL CONCRETE PIPES. THE PIPE SHALL BE CLEAN AND MOIST WHEN MORTAR IS APPLIED. THE LOWER PORTIONS OF THE BELL OR GROOVE SHALL BE FILLED WITH MORTAR SUFFICIENT TO BRING THE INNER SURFACE FLUSH AND EVEN WHEN THE NEXT JOINT IS FITTED INTO PLACE. THE REMAINDER OF THE JOINT SHALL THEN BE FILLED WITH MORTAR AND A BEAD OR RING OF MORTAR FORMED AROUND THE OUTSIDE OF THE JOINT. THE APPLICATION OF MORTAR MAY BE DELAYED UNTIL FILL IS COMPLETED WHEN THE PIPE IS LARGER THAN THIRTY (30) INCHES.

8. PREFORMED JOINT SEALER, WHICH CONFORMS TO AASHTO SPECIFICATION M-198 FOR TYPE B FLEXIBLE PLASTIC GASKETS, MAY BE USED IN LIEU OF THE MORTAR JOINING METHOD.

9. PVC PIPE FITTINGS AND MATERIAL SHALL CONFORM TO AASHTO M304.

10. THE INTERIOR SURFACES OF ALL STORM DRAINAGE STRUCTURES SHALL BE POINTED UP AND SMOOTHED TO AN ACCEPTABLE STANDARD USING MORTAR MIXED TO MANUFACTURER'S SPECIFICATIONS

11. ALL PIPES IN STORM DRAIN STRUCTURES SHALL BE FLUSH WITH THE INSIDE WALL.

12. ANY STORM DRAIN STRUCTURES OVER THREE (3) FEET AND SIX (6) INCHES IN HEIGHT MUST HAVE STEPS IN ACCORDANCE WITH SCDOT STANDARD SPECIFICATIONS.

13. ALL FRAMES, GRATES, RINGS, COVERS, ETC., MUST CONFORM TO SCDOT STANDARD SPECIFICATIONS.

14. ALL GRADED SLOPES SHALL BE AT A MAXIMUM OF TWO (2) FEET HORIZONTAL TO ONE (1) FOOT VERTICAL (2:1) AND NOT TO EXCEED 10' WITHOUT TERRACING.

15. ALL BACKFILL SHALL BE NON-PLASTIC IN NATURE, FREE FROM ROOTS, VEGETATIVE MATTER, WASTE, CONSTRUCTION MATERIAL OR OTHER OBJECTIONABLE MATERIAL, SAID MATERIAL SHALL BE CAPABLE OF BEING COMPACTED BY MECHANICAL MEANS AND SHALL HAVE NO TENDENCY TO FLOW OR BEHAVE IN A PLASTIC MANNER UNDER THE TAMPING BLOWS OR PROOF ROLLING.

16. MATERIALS DEEMED BY THE GEOTECHNICAL ENGINEER AS UNSUITABLE FOR BACKFILL PURPOSES SHALL BE REMOVED AND REPLACED WITH SELECT BACKFILL MATERIAL.

17. BACKFILLING OF TRENCHES SHALL BE ACCOMPLISHED IMMEDIATELY AFTER THE PIPE IS LAID. THE FILL AROUND THE PIPE SHALL BE PLACED IN LAYERS NOT TO EXCEED EIGHT (8) INCHES, EACH LAYER SHALL BE THOROUGHLY COMPACTED TO 95 % OF THE MAXIMUM DENSITY OBTAINABLE WITH THE STANDARD PROCTOR TEST (A DENSITY OF 100 % STANDARD PROCTOR IS REQUIRED FOR THE TOP EIGHT (8) INCHES).

18. COMPACTION REQUIREMENTS SHALL BE ATTAINED BY THE USE OF MECHANICAL COMPACTION METHODS. EACH LAYER OF BACKFILL SHALL BE PLACED LOOSE AND THOROUGHLY COMPACTED IN PLACE.

19. UNDER NO CIRCUMSTANCES SHALL WATER BE PERMITTED TO RISE IN UNBACKFILLED TRENCHES AFTER THE PIPE HAS BEEN PLACED.

20. RIM FOR CATCH BASIN (CB) = TOP BACK OF CURB.

21. RIM FOR DROP INLET (DI) = TOP CENTER OF GRATE.

SCDHEC STANDARD NOTES:

1. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.

2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW

- WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS
- SOON AS PRACTICABLE WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.

3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.

4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION, ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.

5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL FROSION AND/OR OFESITE SEDIMENTATION, ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.

6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.

7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C REG. 72-300 ET SEQ. AND SCR100000.

8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.

9. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WATERS OF THE STATE.

10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.

11. A COPY OF THE SWPPP, INSPECTIONS RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.

12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.

13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.

14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING. WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE;

15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.).

16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:

- WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN
- APPROPRIATE CONTROL WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM
- RELEASE OILS CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS • FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT
- OPERATION AND MAINTENANCE; AND • SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.

17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.

18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.

19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

SCDHEC SPILL PREVENTION AND RESPONSE NOTES:

CLEANUP AND STORAGE PROCEDURES:

1. IF A SPILL OCCURS, DEMOBILIZE IT AS SOON AS POSSIBLE.

2. IF THERE IS A CHANCE THAT THE SPILL COULD ENTER A STORM DRAIN OR SEWER, PLUG THE INLET AND TURN OFF OR DIVERT ANY INCOMING WATER.

3. COVER THE SPILL WITH ABSORBENT MATERIAL SUCH AS KITTY LITTER OR SAWDUST. DO NOT USE STRAW. DISPOSE OF THE USED ABSORBENT PER MANUFACTURER'S INSTRUCTIONS. IF THE SPILL IS FLAMMABLE, DISPOSE OF AS DIRECTED BY THE LOCAL FIRE MARSHAL.

4. KEEP THE AREA WELL VENTILATED.

5. MINOR SPILLS - MINOR SPILLS TYPICALLY INVOLVE SMALL QUANTITIES OF OIL, GASOLINE, PAINT, ETC., WHICH CAN BE CONTROLLED BY THE FIRST RESPONDER AT THE DISCOVERY OF THE SPILL. USE ABSORBENT MATERIALS ON SMALL SPILLS RATHER THAN HOSING DOWN OR BURYING THE SPILL

6. SEMI-SIGNIFICANT SPILLS - SEMI-SIGNIFICANT SPILLS STILL CAN BE CONTROLLED BY THE FIRST RESPONDER ALONG WITH THE AID OF OTHER PERSONNEL SUCH AS LABORERS AND THE FOREMAN, ETC. THIS RESPONSE MAY REQUIRE THE CESSATION OF ALL OTHER ACTIVITIES.

- 7. CONTAIN SPILLS IMMEDIATELY:
- a. IF THE SPILL OCCURS ON PAVED OR IMPERMEABLE SURFACES, CLEAN UP USING "DRY" METHODS (ABSORBENT MATERIALS, CAT LITTER AND/OR RAGS). CONTAIN THE SPILL BY ENCIRCLING WITH ABSORBENT MATERIALS AND DO NOT LET THE SPILL SPREAD WIDELY. b. IF THE SPILL OCCURS IN DIRT AREAS, IMMEDIATELY CONTAIN THE SPILL BY CONSTRUCTING
- AN EARTHEN DIKE. c. IF THE SPILL OCCURS DURING RAIN, TO THE EXTENT THAT IT DOESN'T COMPROMISE CLEAN-UP ACTIVITIES, COVER SPILL WITH TARPS OR OTHER MATERIAL TO PREVENT CONTAMINATING RUNOFF.

8. SIGNIFICANT/HAZARDOUS SPILLS - FOR SIGNIFICANT OR HAZARDOUS SPILLS THAT CANNOT BE CONTROLLED BY PERSONNEL IN THE IMMEDIATE VICINITY. THE SERVICES OF A SPILLS CONTRACTOR OR A HAZ-MAT TEAM SHOULD BE OBTAINED IMMEDIATELY. CONSTRUCTION PERSONNEL SHOULD NOT ATTEMPT TO CLEAN UP THE SPILL UNTIL THE APPROPRIATE AND QUALIFIED STAFF HAS ARRIVED AT THE JOB SITE.

9. SPILLS SHOULD NOT BE BURIED OR WASHED WITH WATER.

10. USED CLEAN UP MATERIALS, CONTAMINATED MATERIALS, AND RECOVERED SPILL MATERIAL THAT ARE NO LONGER SUITABLE FOR THE INTENDED PURPOSE SHOULD BE STORED AND DISPOSED OF PROPERLY.

11. WATER USED FOR CLEANING AND DECONTAMINATION SHOULD NOT BE ALLOWED TO ENTER STORM DRAINS OR WATERCOURSES AND SHOULD BE COLLECTED AND DISPOSED OF AS DESCRIBED IN LIQUID WASTE MANAGEMENT.

12. PROPER STORAGE, CLEAN-UP AND SPILL REPORTING INSTRUCTIONS FOR HAZARDOUS MATERIALS STORED OR USED ON THE PROJECT SITE SHOULD BE POSTED AT ALL TIMES IN AN OPEN, CONSPICUOUS AND ACCESSIBLE LOCATION.

13. WASTE STORAGE AREAS SHOULD BE KEPT CLEAN, WELL-ORGANIZED AND EQUIPPED WITH AMPLE CLEAN-UP SUPPLIES AS APPROPRIATE FOR THE MATERIALS BEING STORED. PERIMETER CONTROLS, CONTAINMENT STRUCTURES, COVERS AND LINERS SHOULD BE REPAIRED OR REPLACED AS NEEDED TO MAINTAIN PROPER FUNCTION.

INSPECTION AND MAINTENANCE:

1. VERIFY WEEKLY, THAT SPILL CONTROL CLEAN UP MATERIALS ARE LOCATED NEAR MATERIAL STORAGE, UNLOADING AND USE AREAS.

2. UPDATE SPCC PLANS AND STOCK APPROPRIATE CLEAN-UP MATERIALS WHENEVER CHANGES OCCUR IN THE TYPES OF CHEMICALS USED OR STORED ONSITE.

TO REPORT CHEMICAL SPILLS, OIL SPILLS, OR FISH KILLS CALL OUR TOLL-FREE 24-HOUR EMERGENCY RESPONSE LINE AT 1-888-481-0125

UTILITY NOTES:

1. EXISTING UTILITIES SHOWN ARE FOR THE CONTRACTOR'S CONVENIENCE ONLY. THERE MAY BE OTHER UTILITIES NOT SHOWN ON THIS PLAN; THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE LOCATIONS SHOWN. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES PRIOR TO COMMENCEMENT OF CONSTRUCTION. CONFLICTS BETWEEN EXISTING UTILITIES AND PROPOSED EXCAVATION SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY.

2. PROVIDE MINIMUM OF 48 HOUR NOTICE TO OWNER OR REPRESENTATIVE PRIOR TO INTERRUPTION OF ANY EXISTING UTILITY, IF BEING UTILIZED.

3. THE CONTRACTOR IS RESPONSIBLE FOR REPAIR AND/OR REPLACEMENT OF ANY UTILITIES DAMAGED DURING CONSTRUCTION. CONTRACTOR IS TO MAINTAIN UTILITY SERVICES, INCLUDING WATER, SANITARY SEWER, STORM SEWER, NATURAL GAS, ELECTRIC AND TELEPHONE AT ALL TIMES DURING CONSTRUCTION.

4. CONTRACTOR IS TO KEEP ALL PARKING AREAS, ALLEYS, DRIVEWAYS AND STREETS ADJACENT TO THE CONSTRUCTION SITE CLEAN AT ALL TIMES DURING CONSTRUCTION.

5. CONTRACTOR SHALL ADJUST THE ELEVATION OF THE RINGS AND COVERS OF ALL EXISTING UTILITIES WHICH ARE TO REMAIN AND ARE TO MATCH PROPOSED/FINAL GRADES. CONTRACTOR SHALL ALSO MATCH AT GRADE UTILITIES TO FINAL PROJECT GRADES UNLESS OTHERWISE

6. ALL SIGNS WITHIN THE LIMITS OF CONSTRUCTION MAY BE REMOVED AS NEEDED FOR THE CONSTRUCTION AND REPLACED AS SOON AS POSSIBLE. TEMPORARY FREESTANDING SIGNS MAY BE NEEDED/REQUIRED DURING CONSTRUCTION.

7. SIGNING OF THE CONSTRUCTION AREA SHALL COMPLY WITH THE CURRENT " MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS". ALL SIGNAGE INCLUDING REGULATORY AND WARNING SIGNS ARE TO REMAIN THROUGHOUT THE DEMOLITION AND CONSTRUCTION PHASES. ALL SIGNS WHICH NEED TO BE REMOVED ARE TO BE RELOCATED IMMEDIATELY

8. CONTRACTOR TO SET UP TEMPORARY SEDIMENT CONTROL MEASURES BEFORE WORK COMMENCES. ALL EROSION CONTROL MEASURES SHALL BE INSPECTED DAILY (MONDAY THROUGH FRIDAY) FOR EXCESSIVE SILT. CONTRACTOR SHALL REMOVE EXCESSIVE SILT FROM THE DEVICES IMMEDIATELY BEFORE CONSTRUCTION COMMENCES ON THAT DAY. MAINTENANCE SHALL CONTINUE THROUGH PROJECT COMPLETION.

9. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL NECESSARY PERMITS AND APPROVALS HAVE BEEN OBTAINED PRIOR TO CONSTRUCTION. THESE PERMITS AND APPROVALS MAY INCLUDE BUT ARE NOT LIMITED TO GRADING, DEMOLITION, ZONING, BUILDING, DRIVEWAY, DETENTION, SUBDIVISION, SPECIAL USE, SEWER AND WATER.









T14.400 - Lincoln Rd Sidewalk_KT14\Sheets\KT14-SWLKPP.dwg, PLAN & PROFILE 1, snsabi

KT14.400 - Lincoln Rd Sidewalk_KT14\Sheets\KT14-SWLKPP.dwg, PLAN & PROFILE 3, snsabua

T14.400 - Lincoln Rd Sidewalk_KT14\Sheets\KT14-DETAILS.dwg, DETAILS, snsabu

	DESCRIPTION	STRENGTH (F'C)	WEIGHT	
	CAST-IN-PLACE CONCRETE	5000 PSI	145 PCF	
F.	CONCRETE MIX DESIGNS SHALL B	E PREPARED AND S	UBMITTED 30 DAYS PRIOR TO STAR	IT O
	C150-TYPE 1, NORMAL WEIGHT AC	GREGATE SHALL CO	ONFORM TO ASTM C33 AND LIGHT V	NEIG

- D, THE MIN, 28 DAY COMPRESSIVE STRENGTH OF THE CONC. SHALL BE 3,600 PSI.
- E, CONC, SLUMP AT THE PLACEMENT POINT SHALL BE IN THE RANGE OF 3" TO 5". F. PLACEMENT OF CONC. INCLUDING SLUMP, MECH. VIBRATION, AND CALCIUM CHLORIDE CONTENT SHALL BE IN ACCORDANCE W/ ACI 301.
- G, CONC, COVER ON REINF, STEEL SHALL MEET THE FOLLOWING REQUIREMENTS UNLESS NOTED OTHERWISE: CONC. CAST AGAINST AND PERMANENTLY EXPOSED EARTH = 3" 1.
- 2. CONC. CAST AGAINST FORMS AND EXPOSED TO EARTH = 3"
- 3. CONC. EXPOSED TO WEATHER = 3''

<u>SANDY SOIL</u> (SM)

- 1- DENSE ANGULAR GRAIN SILTY SAND,
 - A. \bigvee DID RATION = e = 0.4
 - B. MOISTURE CONTENT CONDITION = 15%
 - C. DRY UNIT WEIGHT = 120 LBS/CU. FT.
 - D. UNIT WEIGHT OF MOIST SOIL = 138 LBS/CU. FT.
 - E, COMPRESSABILTY AND EXPANSION = SLIGHT,
 - F. VALUE AS EMBANKMENT MATERIAL = REASONABLY STABLE WHEN DENSE.
 - G. VALUE SUB-GRADE MATERIAL = GOOD TO FAIR
- H, RELATIVE DENSITY = 60% TO 80% % RETAINED ON #4 SIEVE = R < 0.5 R

artner In Charg ABW Project Enginee Drawn By Date Drawn 9-27-2023 AININ S BOX YOR K FOR ALK OF SIDEW. END RD CONC INOLN <u>o</u> <u>a</u> 91 5 S <u>ა რ</u> ς 2 4 0 Beacl Fax. **L** ち Street, Myrtl 448.3428 Ο ы С roject Number WE-23-258 ^{et} S1.0

(STA. 1+00)

۲۲14.400 - Lincoln Rd Sidewalk_KT14\Sheets\KT14-ROAD X-SEC.dwg, CROSS-SECTIONS (SHEET 2 OF 5), snsε

(STA. 17+80 - DRIVEWAY)

-EXIST. GRADE

(STA. 25+00)

VERTICAL GRAPHIC SCALE

(IN FEET) 1 INCH = 5 FT.

South C Health an	arolin d Env	a De _l vironn	partm nental	ent Co	: of ontr	ro
	SILT	FEN	VCE			
STANDARD DRAWING N	10. SC-	03	PAGE	2	of	2
	A I		- FFF	RUARY	2014	

N	COORDINATE WORK AT INTERSECTION TO MAINTAIN ADEQUATE TRAFFIC FLOW; MIN. ONE LANE TO REMAIN OPEN
	AREA OF CLOSURE 1 SEE SCDOT DETAILS 602-005-00 (SIGNING)
H	
LILSINE	MAMIE LYNN JOHNSON DB. 112–142 PID# 07002 KARLA KOESTER & PAMELA ALANE VOESTER CARPISON DB. 11118–115 DB. 11118–115 DB. 11118–115 DB. 11118–115 DB. 11118–115 DB. 11118–115
<i>\</i>	10023 DB. 11118-115 ROESTER GARRISON DB. 11158-321 DB. 11158-321 DB. 1158-321 DB. 19655-13 PID# 0700210015 PID# 0700210026 PID# 0700210027 PID# 0700210027
4	
	HABITAT FOR HUMANITY OF YORK COUNT
	PB. E283-2 PD# 0700506002 PD# 0700506002 PD# 0700506002 PD# 0700506002
CONGRESS	Top ao. 50' SPACING
	TREET &
	250,00° TAP
	W21
	500.00
	NOTES /
	1. CONTRACTOR TO PHASE WORK AREA CLOSURES WITH MINIMAL DISTURBANCE TO PROPERTY OWNERS. /
	2. CONTRACTOR TO COORDINATE WORK AT DRIVEWAYS WITH PROPERTY OWNERS.
	TRAFFIC CONTROL NOTES 1. CONTRACTOR SHALL NOTIFY LOCAL GOVERNING ENGINEERING DIVISION AND SCDOT A
	MINIMUM OF FIVE (5) DAYS PRIOR TO BEGINNING CONSTRUCTION.
	PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH THE THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES HANDBOOK (MUTCD).
	3. THE CONTRACTOR SHALL MAINTAIN TRAFFIC IN ACCORDANCE WITH ALL SCDOT REGULATIONS.
	4. VEHICULAR ACCESS SHALL BE MAINTAINED TO ALL PROPERTIES, BUSINESSES, DWELLINGS, SCHOOLS, POLICE STATIONS, FIRE STATIONS, HOSPITALS, AND FIRE HYDRANTS, AND ANY OTHER EMERGENCY SERVICES, AND MAILBOXES AFFECTED BY THE
	PROJECT. 5. ALL RADII SHOWN ON THIS PLAN ARE MEASURED AT THE BACK OF CURB, UNLESS
	6. RAISED REFLECTORIZED PAVEMENT MARKERS(RPM'S) SHALL BE PLACED AT ALL PAVEMENT, MARKINGS AND SHALL BE PLACED IN ACCORDANCE WITH THE SCOOT
	STANDARDS. 7 CONTRACTOR IS RESPONSIBLE FOR OBTAINING LOCATIONS OF EXISTING UTILITIES PRIOR
	TO COMMENCEMENT OF CONSTRUCTION. CONTRACTOR RESPONSIBLE FOR COORDINATION WITH POWER COMPANY AND/OR CABLE TV/PHONE COMPANIES TO RELOCATE EXISTING OVERHEAD AND UNDERGROUND UTILITIES, CONTRACTOR TO COORDINATE WITH YORK
	COUNTY PUBLIC WORKS DEPARTMENT REGARDING WATER/SANITARY SEWER LOCATIONS AND RELOCATIONS. CONTRACTOR TO COORDINATE WITH YORK COUNTY NATURAL GAS CO. REGARDING LOCATION AND RELOCATION. IF REQUIRED, OF NATURAL GAS LINES.
	8. DEVELOPER/OWNER RESPONSIBLE FOR COORDINATION WITH ALL ADJOINING PROPERTY OWNERS PRIOR TO CONSTRUCTION.
	9. EXISTING SIGNAGE (SPEED LIMIT, SCHOOL, ETC.) TO BE REPLACED/MOVED AS REQUIRED BY STREET WIDENING
	10. SURVEY INFORMATION SUPPLIED BY ESP ASSOCIATES, INC.
	11. CONTRACTOR IS RESPONSIBLE FOR RELOCATION OF ALL UTILITIES AS NECESSARY. COORDINATE WITH APPROPRIATE UTILITY OWNERS.
	12. CONTRACTOR IS RESPONSIBLE FOR RELOCATION OF EXISTING FENCES, MAILBOXES, AND OTHER AFFECTED STRUCTURES.
	13. DEVELOPER/OWNER IS RESPONSIBLE FOR OBTAINING REQUIRED EASEMENTS AND/OR RIGHT OF WAY FROM AFFECTED ADJACENT PROPERTY OWNERS PRIOR TO CONSTRUCTION.
	14. CONTRACTOR IS RESPONSIBLE FOR EROSION CONTROL AND STABILIZATION AS REQUIRED BY EROSION CONTROL PLANS.
	LEGEND
	PROP. WORK AREA
	PROP. TRAFFIC CONE
	PROP. FLAGGER

